



## **Addendum No. 1**

February 7, 2019

Walk-in Freezer Replacement – Roosevelt Middle School

Bid Number 180-18/19

This addendum supercedes, supplements and has precedence over all portions of the bidding documents with which it differs. Acknowledge receipt of this Addendum in the space provided on Bid Form, paragraph 9. Failure to do so may subject the Bidder to disqualification.

### **Changes to the Scope of Work and Equipment/Parts:**

- Demo existing concrete pad and base, compact and pour new 6” slab. Maintain all existing elevations.
- All new box outer dimensions: Width 9’ Length 19’ High 8’.
- Open space above top of the freezer box to be covered with embossed galvanized to the ceiling.
- GUSD will provide power and disconnect switch on the roof for the condensing unit.
- Contractor responsible to run power from disconnect to the condensing unit.
- Contractor responsible to provide and install a 3-phase 460v. to a single phase 230 v. 20 Amp. step-down transformer and run the electrical from condenser to the evaporator coil.
- Condensing unit Model # TEZA055LHT4CF Trenton Scroll C/U L/T 5, 5 HP Multiref 460/3-phase With Pressure Controls, Timer, Sight Glass and Dryer.
- Provide and install lock bar and key lock for freezer door.
- Freezer door to be right hand. (Swing to the right).

End of Addendum No. 1