

PAVING AND STRIPING PROJECT

Verdugo Woodlands

Per attached Plan provided the attached scope of work:

- Demolish Asphalt Ramps and repair damages where Relocatable Buildings were removed; repair cracks over ¼”.
- Install Base or grindings and Asphalt minimum 3” each to match existing elevation.
- Clean, prep and slurry coat entire Asphalt Play area.
- Stripe Playground per Plans.
- Clean and dispose of all debris

Additive Alternates

- Install/Adjust Basketball Goals per plan.
- Provide and install Sleeves for Volleyball Post per plans